MARYLAND HISTORICAL TRUST NR-ELIGIBILITY REVIEW FORM

NR	Eligible:	yes	
		no	

Property Name: Ensor House Inventory Number: BA-2048
Address: 16947 York Road City: Monkton Zip Code: 21102
County: Baltimore USGS Topographic Map: Hereford, MD
Owner: Randolph H. Shelley and Yvonne E. Shelley
Tax Parcel Number: 172 Tax Map Number: 22 Tax Account ID Number:
Project: Hereford Tower Project Agency: FCC
Site visit by MHT Staff: X no yes Name: Date:
Eligibility recommended Eligibility not recommended
Criteria:ABCD Considerations:A_BCD_E_F_GNone
Is the property located within a historic district? X no yes Name of district:
Is district listed? X noyes Determined eligible? X noyes District Inventory Number:
Documentation on the property/district is presented in: MIHP form; Rotenstein 2000
The Ensor House is a two-story wood frame building constructed on a masonry wall foundation. Measuring three bays by three bays, this Italianate house has a shed roof front porch and two interior brick chimneys. The building's shed roof is clad by standing seam metal and the building is clad by asbestos shingles. Decorative elements include a two-light transom above the front entry and a bracketed cornice pediment. There are several additions to the house, including a rear shed roof addition and side (north) addition. Also, there is a rear wood deck and wood stairs. Although the MIHP form completed in 1980 suggests that this building was constructed between ca. 1825 and 1833, its form and stylistic elements suggest a later date: ca. 1850-1870. The house, during the 1870s, was used as a hotel by owner Nathan Ensor. During the twentieth century, the building was converted into retail shops and services. In 1980, it housed a barbershop. Currently occupants include a restaurant and construction contractors. This property does not retain its architectural integrity and does not appear to be related to any significant individuals or events in Hereford's history. This property appears to be not eligible for listing in the National Register of Historic Places.
Prepared by: David S. Rotenstein Date Prepared: 09/07/2000
MARYLAND HISTORICAL TRUST REVIEW Eligibility recommended Eligibility not recommended
Criteria: A B C D Considerations: A B C D E F G None Comments:
OPNUM 11/16/2001
Reviewer, Office of Preservation Services Date

Maryland Historical Trust Maryland Inventory of Historic Properties Form

Inventory No.

BA-2048

1. Name of P	roperty	(indicate prefe	rred name)		
historic	Ensor H	ouse			
other	Costa Ba	arbershop			
2. Location					
street and number	16947 Y	ork Road		not for	publication
city, town	Monkton			vicinity	
county	Baltimo:	re			
3. Owner of F	Property	(give names and m	ailing addresses of all own	ers)	
name	Randolpl	n H. Shelley and	Yvonne E. Shelley		
street and number	2601 Cot	ter Road		telephone	
city, town	Millers		state MD	zip code 21	L102
courthouse, registry	of deeds, etc.	Baltimore County	Courthouse	tax map and parcel:	
	cation o	f Additional D	ata		
Contributing Res Determined Eligil Determined Inelig Recorded by HAB X Historic Structure Other:	ource in Local I ble for the Natic gible for the Nat 3S/HAER Report or Res	al Register District Historic District Inal Register/Maryland R Ional Register/Maryland earch Report at MHT	•		
6. Classificat					
Category district building(s) structure site object	Ownership public X private both	Current Function agriculture X commerce/trade defense domestic education funerary government health care industry	landscape recreation/culture religion social transportation work in progress unknown vacant/not in use other:	Resource Count Contributing Nonc 1 1 Number of Contrib previously listed in	_

7. Description

Inventory No. BA-2048

Condition

 excellent
 deteriorated

 X
 good
 ruins

 fair
 X
 altered

Prepare both a one paragraph summary and a comprehensive description of the resource and its various elements as it exists today.

The Ensor House is a two-story wood frame building constructed on a masonry wall foundation. Measuring three bays by three bays, this Italianate house has a shed roof front porch and two interior brick chimneys. The building's shed roof is clad by standing seam metal and the building is clad by asbestos shingles. Decorative elements include a two-light transom above the front entry and a bracketed cornice pediment. There are several additions to the house, including a rear shed roof addition and side (north) addition. Also, there is a rear wood deck and wood stairs.

8. Signifi	Areas of Significance	Check and justify below	entory No. BA-20	J48
1600-1699	agriculture archeology X architecture art X commerce communications community planning conservation	economics education engineering entertainment/ recreation ethnic heritage exploration/ settlement	health/medicine industry invention landscape architecture law literature maritime history military	performing arts philosophy politics/governmen religion science social history transportation other:
Specific date	s ca. 1825-195	0 Architect		
Construction	dates 1825-1833	Builder		/-
Evaluation for	or:			
X_ Nati	onal Register	Maryland Register		not evaluated

Prepare a one-paragraph summary statement of significance addressing applicable criteria, followed by a narrative discussion of the history of the resource and its context. (For compliance reports, complete evaluation on a DOE Form - see manual.)

Although the MIHP form completed in 1980 suggests that this building was constructed between ca. 1825 and 1833, its form and stylistic elements suggest a later date: ca. 1850-1870. The house, during the 1870s, was used as a hotel by owner Nathan Ensor. During the twentieth century, the building was converted into retail shops and services. In 1980, it housed a barbershop. Currently occupants include a restaurant and construction contractors. This property does not retain its architectural integrity and does not appear to be related to any significant individuals or events in Hereford's history. This property appears to be not eligible for listing in the National Register of Historic Places.

Maryland Historical Trust Maryland Inventory of Historic Properties Form

Inventory No. BA-2048

Name	Ensor	House	
Continu	ation Sh	eet	
Number	8	_Page	1

HISTORIC CONTEXT

MARYLAND COMPREHENSIVE PRESERVATION PLAN DATA

Geographic Organization:
Chronological/Developmental Period(s):
Historic Period Theme(s):
Resource Type:
Category:
Historic Environment
Historic Function(s) and Use(s):
Known Design Source:

9. Major Bibliographical References

Inventory No. BA-2048

Baltimore County Council (1991); Brooks, N. A., and E. G. Rockel (1979); Clemens and Clemens (1983); McGrain (1980)

10. Geographical Data

Acreage of surveyed property

13,987 sq. ft.

Acreage of historical setting

13,987 sq. ft.

Quadrangle name

Hereford, MD

Quadrangle scale

1:24,000

Verbal boundary description and justification

The boundaries for this property conform to the tax parcel boundary: Map 22, Parcel 172.

11. Form Prepared By

name/title	David S. Rotenstein, Ph.D./Historian		
organization	URS/Dames & Moore	date	09/07/2000
street and number	7101 Wisconsin Avenue, Suite 700	telephone	301-652-221
city or town	Bethesda	state MD	zipcode 20814-4870

The Maryland Inventory of Historic Properties was officially created by an Act of the Maryland Legislature to be found in the Annotated Code of Maryland, Article 41, Section 181 KA, 1974 supplement.

The survey and inventory are being prepared for information and record purposes only and do not constitute any infringement of individual property rights.


return to:

Maryland Historical Trust

DHCD/DHCP

100 Community Place Crownsville MD 21032

410-514-7600





BA-2048 1/2 Enson House Costa Barbershop 16947 York Road Battimore County Maryland David 5, Robenstein View of the Ensor House, to the



BA-2048 2/2 Enson House Costa Berbershop 16947 York Road Baltimore County, Maryland David S Patenstein 8/22/2000 MD SHPO View of the year of the Ensor House, to the northwest.

BA 2048

ENSOR HOUSE/ COSTA BARBERSHOP

1825-1833

HEREFORD

PRIVATE

The Costa-Dwelling and barbershop stands on a lot that has been a consistent 14,000-square-foot size since Solomon Foster sold to Marahb H. Foster in 1837 for \$300, a price that would have permitted a modest town house. This seems to be one of the houses marked on the 1850 map by J.C. Sidney. Nathan G. Ensor bought it in 1867, and appears in the 1877 atlas; the 1878 state directory listed him as a hotel keeper. A substantial dwelling house was advertised that year when Ensor was in fimancial difficulties. It later belonged to Arthur S. Carman, a tinner. John Costa, a barber, acquired it in 1940. This is a flat-roofed, Victorian Italianate commercial building of two stories, with bright green composition shingles, an elaborate entablature, including Italianate bracketing. If this house existed in 1833 or before, it was probably been much improved from its original state before becoming a hotel.

INVENTORY FORM FOR STATE HISTORIC SITES SURVEY

NAME						
HISTORIC	ENSOR	HOUSE	മക്ക	ilaji		
AND/OR COM	1MON					
	Costa	Barbershop				
LOCAT	ION					
 STREET & NU	MBER					
16,947	7 York	Road				
CITY, TOWN	_			CONGRESSIO	NAL DISTR	ICT
Herefo	ord		VICINITY OF	2nd		
state Maryla	and			COUNTY Baltime	ore Co	ountv
CLASS	IFICAT	TION				
CATEG	ORY	OWNERSHIP	STATUS	gar in the last	DDEC	ENT USE
DISTRICT		PUBLIC	XOCCUPIED	AGRICU		MUSEUM
X BUILDING		PRIVATE	UNOCCUPIED	X COMME	_	PARK
STRUCTU	RE	ВОТН	WORK IN PROGRESS	EDUCA		X PRIVATE RESIDENCE
SITE		PUBLIC ACQUISITION	ACCESSIBLE	ENTERT	TAINMENT	RELIGIOUS
OBJECT		IN PROCESS	XYES: RESTRICTED	GOVERI	NMENT	SCIENTIFIC
			V50	_INDUST	T DI A I	TRANSPORTATION
		BEING CONSIDERED	YES: UNRESTRICTED		MIAL	
OWNE			YES: UNRESTRICTED	MILITAI		OTHER:
_		ROPERTY		MILITAI	RY	OTHER:
_	R OF Plon Cos	ROPERTY			RY	OTHER:
NAME J	R OF P	ROPERTY		_MILITAI	#: 35	OTHER:
NAME J STREET & NUI CITY, TOWN	R OF Plon Cos	ROPERTY sta	_NO	_MILITAI Telephone	#: 35	OTHER:
NAME J STREET & NUI CITY, TOWN M	R OF Plon Cos	ROPERTY sta York Road —	NO	_MILITAI Telephone	#: 35	OTHER:
NAME J STREET & NUI CITY, TOWN M	R OF Plon Cos	ROPERTY sta	NO	_MILITAI Telephone	#: 35	OTHER:
NAME J STREET & NUI CITY, TOWN M	R OF Plon Cos MBER 6,947 Sonkton FION O	ROPERTY sta York Road —	_NO VICINITY OF IPTION	_MILITAI Telephone st	#: 35	OTHER:
STREET & NUI CITY, TOWN M LOCAT COURTHOUSE	R OF Plon Cos MBER 6,947 Stonkton FION O E. DEEDS,ETC.	ROPERTY Sta York Road F LEGAL DESCR County Courts	_NO VICINITY OF IPTION Building	Telephone st Ma Liber #:	#: 35 ATE, Z arylar 1088	OTHER:
STREET & NUI CITY. TOWN M LOCAT COURTHOUSE REGISTRY OF STREET & NUI	R OF Plon Cos MBER 6,947 Stonkton FION O E. DEEDS,ETC.	ROPERTY sta York Road F LEGAL DESCR	_NO VICINITY OF IPTION Building	Telephone ST Ma Liber #: Folio #:	#: 35 ATE, Z ATYlar 1088 301	OTHER:
STREET & NUI CITY. TOWN M LOCAT COURTHOUSE REGISTRY OF	R OF Plon Cos MBER 6,947 Stonkton FION O E. DEEDS,ETC.	ROPERTY Sta York Road F LEGAL DESCR County Courts 401 Bosley Ave	_NO VICINITY OF IPTION Building	Telephone ST Ma Liber #: Folio #:	#: 35 ATE, Z ATYlar 1088 301	_OTHER:
STREET & NUI CITY. TOWN M LOCAT COURTHOUSE REGISTRY OF STREET & NUI CITY. TOWN	R OF Plon Cos MBER 6,947 Sonkton FION O E. DEEDS, ETC.	ROPERTY sta York Road — FLEGAL DESCR County Courts 401 Bosley Ave Towson	_NO VICINITY OF IPTION Building nue	Telephone ST Ma Liber #: Folio #:	#: 35 ATE, Z ATYlar 1088 301	OTHER:
STREET & NUI CITY. TOWN M LOCAT COURTHOUSE REGISTRY OF STREET & NUI CITY. TOWN	R OF Plon Cos MBER 6,947 Sonkton FION O E. DEEDS, ETC.	ROPERTY Sta York Road F LEGAL DESCR County Courts 401 Bosley Ave	_NO VICINITY OF IPTION Building nue	Telephone ST Ma Liber #: Folio #:	#: 35 ATE, Z ATYlar 1088 301	_OTHER:
STREET & NUI CITY. TOWN M LOCAT COURTHOUSE REGISTRY OF STREET & NUI CITY. TOWN REPRE TITLE	R OF Plon Cos MBER 6,947 Sonkton FION O E. DEEDS, ETC.	ROPERTY sta York Road — FLEGAL DESCR County Courts 401 Bosley Ave Towson	_NO VICINITY OF IPTION Building nue	Telephone ST Ma Liber #: Folio #:	#: 35 ATE, Z ATYlar 1088 301	_OTHER:
STREET & NUI CITY. TOWN M LOCAT COURTHOUSE REGISTRY OF STREET & NUI CITY. TOWN REPRE TITLE	R OF Plon Cos MBER 6,947 S Onkton TION O E. DEEDS,ETC. MBER	ROPERTY sta York Road — FLEGAL DESCR County Courts 401 Bosley Ave Towson	VICINITY OF IPTION Building nue	Telephone ST Ma Liber #: Folio #:	#: 35 ATE, Z ATYlar 1088 301 ATE Iaryla	_OTHER:
STREET & NUI CITY. TOWN M LOCAT COURTHOUSE REGISTRY OF STREET & NUI CITY. TOWN REPRE TITLE NO DATE	R OF Plon Cos MBER 6,947 S ONE SENTA ONE	ROPERTY sta York Road — FLEGAL DESCR County Courts 401 Bosley Ave Towson	VICINITY OF IPTION Building nue	Telephone ST Ma Liber #: Folio #:	#: 35 ATE, Z ATYlar 1088 301 ATE Iaryla	_OTHER:
STREET & NUI CITY. TOWN M LOCAT COURTHOUSE REGISTRY OF STREET & NUI CITY. TOWN REPRE TITLE NO DATE	R OF Plon Cos MBER 6,947 S ONE SENTA ONE	ROPERTY sta York Road — FLEGAL DESCR County Courts 401 Bosley Ave Towson	VICINITY OF IPTION Building nue	Telephone ST Ma Liber #: Folio #:	#: 35 ATE, Z ATYlar 1088 301 ATE Iaryla	_OTHER:

CONDITION

CHECK ONE

CHECK ONE

X_EXCELLENT __GOOD

__FAIR

__DETERIORATED

__UNEXPOSED

___RUINS

XUNALTERED (?) __ALTERED

X_ORIGINAL SITE

__MOVED

DESCRIBE THE PRESENT AND ORIGINAL (IF KNOWN) PHYSICAL APPEARANCE

The Ensor-Costa House or Shop is an L-shaped, two-story, flat-roofed Italianate-Victorian commercial building designed to provide dwelling space on the second floor. structure may be a house of c. 1825, heavily reworked in Victorian style, or it may be a replacement structure built new about 1870. It consists of a two-story main block three bays wide, a two-story rear wing, and a one-story, north wing containing the barber shop.

The main block is three bays wide, two bays deep on the south, four bays deep on the north. There is a fullwidth front porch, shed-roofed, supported by four square posts and two recessed posts, each decorated at the top with scroll brackets. The porch has a plain architrave, a cornice, and Italianate bracketing. The deck is three steps above grade. The space under the deck is screened by concrete block in-fill. The posts rest on stone piers. Porch railing is wrought iron, of severe contemporary design.

The dwelling entrance is in the middle door, which is provided with a large, one-sheet glass light; there is also a protective screen and storm door of aluminum, recent vintage. The windows on either side are floor-to-ceiling types of 4-over-4 double-hung sash types, flanked by decorative shutters of vertically aligned board.

The three upper windows of the main block are 2-over-1 double-hung sash types.

The house is topped by a decorative architrave, cornice, and heavy Italianate bracketing, which also continues around on both sidewalls for their entire depth.

The long leg of the "L" is four bays deep, all available positions filled with windows similar to the others. The short side of the "L" is two bays deep, all four possible positions filled with typical windows; the two windows at first-story south level are fitted with aluminum awnings. In the inner angle between the legs of the "L", there is a one-story, shed-roofed, enclosed porch formed with contemporary aluminum frame windows and a side door.

The entire house is covered with green composition shingles. The shed-roofed, one-room barber shop is tacked on the north end of the house, flush with the front wall. It is two bays on the street facade. The entrance is a gable-roofed vestibule with a 1-over-1 sash window facing

CONTINUATION SHEET NO. 1, ITEM 7, PAGE 2

ENSOR HOUSE

the street. The window is flanked by traditional lighted barber poles mounted on brackets; the door faces the south. The main window of the shop is a very long plate glass window in a heavy wooden frame. The street facade has an architrave, cornice, and brackets similar to the main block. The wing stands on a stone foundation. The main foundation is quite low, of stone, heavily coated with paint.

8 SIGNIFICANCE

FRIOD	AREAS OF SIGNIFICANCE CHECK AND JUSTIFY BELOW				
PREHISTORIC 1400-1499 1500-1599	ARCHEOLOGY-PREHISTORICARCHEOLOGY-HISTORICAGRICULTURE	COMMUNITY PLANNING CONSERVATION ECONOMICS	LANDSCAPE ARCHITECTURELAWLITERATURE	RELIGIONSCIENCESCULPTURE	
1600-1699 1700-1799 <u>X</u> _1800-1899 1900-	XARCHITECTURE ART X_COMMERCE COMMUNICATIONS	EDUCATIONENGINEERINGEXPLORATION/SETTLEMENTINDUSTRYINVENTION	MILITARYMUSICPHILOSOPHYPOLITICS/GOVERNMENT	SOCIAL/HUMANITARIAN THEATER TRANSPORTATION OTHER (SPECIFY)	

SPECIFIC DATES

1825-1833

BUILDER/ARCHITECT

STATEMENT OF SIGNIFICANCE

The Costa House stands on a lot that has been consistently recorded as 14,000 square feet on the eastside of York Road since Solomon Foster sold it to Marab H. Foster in 1837 for \$300. The price should have been permitted a modest house for those times. (1)

In 1851, William Hurst and his wife, Marab Hurst, sold to William Johnson for \$223. (2) Johnson's name appears on or near this property on the 1850 map by J. C. Sidney. Johnson sold a few months later to Ephraim Cox for \$450. (3) None of these owners can be found in assessment books of 1833, 1841, or 1852.

This property was in the hands of Francis M. and Almira Hawkins in 1867 when they sold to Nathan G. Ensor for \$550. (4) Ensor mortgaged the property and it was shown as his in the 1877 atlas. The 1878 State directory listed N. G. Ensor as a hotel keeper at Hereford. (5) In March of 1878, Ensor's interest in the 14,000 square-foot-lot was sold at public auction; the only description in the advertisement stated that the ground was "Improved by a confortable and substantial DWELLING HOUSE." (6) There was no mention of a hotel in the 1876 tax ledger. (7)

John T. Mays bought the place at auction. (8) In 1881, Sarah E. Carman bought the house. (9) The 1896 tax ledger charged the house to A. /Arthur/ S. Carnen (sic) and the 1878 State directory had shown A. S. Carman as a tinner. (10)

Mrs. Carman sold in 1914 to Laura T. Howard. (11) The 1918 tax ledger showed William E. Howard with a lot adjoining Charles E. Lloyd on the north (which checks out with the adjoining Store Lot). Howard owned:

Dwelling 20 x 20 1 story
18 x 32 16 x 16 - 2 stories \$1164
1 Outbuilding 200
\$1515. (12)

CONTINUATION SHEET NO. 1, ITEM 8, PAGE 2

ENSOR HOUSE

Mrs. Howard conveyed to George N. Howard in 1919, and George Howard and wife conveyed to George A. Bull in 1923. (13) The Bulls conveyed to John E. and Ada Foster in 1926 and the place passed to W. Delamere Akehurst and wife in 1931 and to the present owner, John Costa, in 1940.

Mr. Costa operates Johnny's Barber Shop on the ground floor. There has apparently been a valuable house on this lot since some point between 1823 and 1825, but the Italianate style of the structure raises the question of whether an entirely new building replaced the 1825 structure during the Victorian era. This is very likely the "comfortable and substantial dwelling house" lost through default by Nathan G. Ensor in 1878. None of the tax lists contain the clue needed to prove that Ensor's flat-roofed "town house" replaced any more rural structure of early Hereford.

NOTES:

- 1. Baltimore City Deeds, TK 278:280.
- 2. Baltimore City Deeds, AWB 468:384.
- 3. Baltimore City Deeds, AWB 468:368.
- 4. Baltimore County Deeds, JB 86:246.
- 5. Frank Lewis & Co., Maryland Directory (Baltimore, 1878), p. 530.
- 6. Maryland Journal, Towson, March 16, 1878, p. 4.
- 7. Assessor's Field Book, District 7, 1876, n.p.
- 8. B.C. Deeds, WMI 147:152.
- 9. B.C. Deeds, WMI 146:261.
- 10. Tax Ledger, District 7, 1896, Entry #133-26.
- 11. B.C. Deeds, WPC 433:537.
- 12. Tax Ledger, District 7, 1818, f. 567.
- 13. B.C. Deeds, WPC 567:304.

MAJOR BIBLIOGRAPHICAL REFERENCES

ENSOR HOUSE

Baltimore County Deed Books and Tax Lists.

CONTINUE ON SEPARATE SHEET IF NECESSARY

10 GEOGRAPHICAL DATA

ACREAGE OF NOMINATED PROPERTY 14,000 sq. feet

VERBAL BOUNDARY DESCRIPTION

Rectangular parcel fronting 70 feet on eastside of York Road with even depth of 200 feet.

STATE NONE COUNTY NONE

STATE NONE

STATE COUNTY NONE

NONE

NONE

NONE

NONE

NONE

NOME

TORM PREPARED BY

NAME / TITLE

JOHN W. McGrain, Sites Surveyor

ORGANIZATION


DATE

John W. McGrain, Sites Surveyor	
ORGANIZATION	DATE
Baltimore County Office of Planning & Zoning	March 14, 1980
STREET & NUMBER	TELEPHONE
401 Bosley Avenue	494-3495
CITY OR TOWN	STATE
Towson	Maryland 21204

The Maryland Historic Sites Inventory was officially created by an Act of the Maryland Legislature, to be found in the Annotated Code of Maryland, Article 41, Section 181 KA, 1974 Supplement.

The Survey and Inventory are being prepared for information and record purposes only and do not constitute any infringement of individual property rights.

RETURN TO: Maryland Historical Trust
The Shaw House, 21 State Circle
Annapolis, Maryland 21401
(301) 267-1438





ENSOR HOUSE (COSTA BARBER SHOP)
Balto. Co., Md. BA 2048
J. McGrain, Oct 1979

Neg. located at MHT Main (west) facade & north wing



ENSOR HOUSE (COSTA BARBER SHOP)
Balto. Co., Md. BA 2048
J. McGrain, OCT 1979
Neg. located at MHT
South facade & main (W) facade



ENSOR HOUSE (COSTA BARBER SHOP)
Balto. Co., Md. BA 2048
J. McGrain, OCT 1979
Neg. located at MHT

Cornice & SW corner of bldg